



NOTE:

1. TOP 6" OF BASE COURSE ON PAVED RESIDENTIAL STREETS & TOP 12" OF PAVED ARTERIAL STREETS TO BE COMPACTED TO 95% MODIFIED PROCTOR.
2. UNPAVED STREETS & OTHER AREAS TO BE 95% MODIFIED PROCTOR.
3. WITHIN CITY ROW PIPE BEDDING & TRENCH BACK FILL SHALL BE BASE COURSE.
4. TRENCH DETAILS FOLLOW OSHA 1926 SUBPART P APP B - EXCAVATION: SLOPING AND BENCHING.



**TRENCH DETAILS
PIPE OVER 72" O.D.**

CONSTRUCTION STANDARDS

STANDARD NO. SS-12

SHEET 2 OF 4

APP'D R. Salcido

DATE Oct. 11, 2023