

PIPE SIZE	TRENCH PAY WIDTH									
	3'	4'	6'	8'	10'	12'	14'	16'	18'	20'
4	5.00	5.00	7.00	9.00	11.00	13.00	15.00	17.00	19.00	21.00
6	5.00	5.00	7.00	9.00	11.00	13.00	15.00	17.00	19.00	21.00
8	5.00	5.00	7.00	9.00	11.00	13.00	15.00	17.00	19.00	21.00
10	5.50	5.50	7.50	9.50	11.50	13.50	15.50	17.50	19.50	21.50
12	5.50	5.50	7.50	9.50	11.50	13.50	15.50	17.50	19.50	21.50
14	5.75	5.75	7.75	9.75	11.75	13.75	15.75	17.75	19.75	21.75
15	5.75	5.75	7.75	9.75	11.75	13.75	15.75	17.75	19.75	21.75
16	5.75	5.75	7.75	9.75	11.75	13.75	15.75	17.75	19.75	21.75
18	6.00	6.00	8.00	10.00	12.00	14.00	16.00	18.00	20.00	22.00
20	6.25	6.25	8.25	10.25	12.25	14.25	16.25	18.25	20.25	22.25
21	6.25	6.25	8.25	10.25	12.25	14.25	16.25	18.25	20.25	22.25
24	6.50	6.50	8.50	10.50	12.50	14.50	16.50	18.50	20.50	22.50
27		6.75	8.75	10.75	12.75	14.75	16.75	18.75	20.75	22.75
30		7.00	9.00	11.00	13.00	15.00	17.00	19.00	21.00	23.00
36		7.50	9.50	11.50	13.50	15.50	17.50	19.50	21.50	23.50
42			10.00	12.00	14.00	16.00	18.00	20.00	22.00	24.00
48			11.50	13.50	15.50	17.50	19.50	21.50	23.50	25.50
54			12.00	14.00	16.00	18.00	20.00	22.00	24.00	26.00
60			12.50	14.50	16.50	18.50	20.50	22.50	24.50	26.50
66				15.00	17.00	19.00	21.00	23.00	25.00	27.00
72				23.50	25.50	27.50	29.50	31.50	33.50	35.50
78				24.00	26.00	28.00	30.00	32.00	34.00	36.00
84				24.50	26.50	28.50	30.50	32.50	34.50	36.50
90				25.00	27.00	29.00	31.00	33.00	35.00	37.00
96				25.50	27.50	29.50	31.50	33.50	35.50	37.50
102				26.00	28.00	30.00	32.00	34.00	36.00	38.00
108				26.50	28.50	30.50	32.50	34.50	36.50	38.50

**NOTE:**

1. PAYMENT FOR PAVEMENT REMOVAL AND REPLACEMENT SHALL BE BASED ON ACTUAL TRENCH WIDTHS UP TO THE WIDTH NOTED ABOVE & WILL BE PAID FOR ACTUAL TRENCH MEASUREMENT.
2. EXCESSIVE TRENCH WIDTH ABOVE THAT LISTED IN THE TABLE ABOVE WILL BE AT THE CONTRACTORS EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE PAID. IF CONDITIONS EXIST THAT REQUIRES ADDITIONAL REMOVAL CONTRACTOR SHALL REQUEST CITY ENGINEER APPROVAL.
3. IN THE EVENT A LINE IS LOCATED SUCH THAT REMOVAL OF CURB, GUTTER AND SIDEWALK IS REQUIRED PAVEMENT WIDTH SHALL BE LIMITED TO 1/2 THE PAY WIDTH PLUS THE DISTANCE FROM THE CENTERLINE OF THE PIPE TO GUTTER. PAYMENT FOR REMOVAL AND REPLACEMENT OF CURB AND SIDEWALK SHALL BE AS MEASURED IN THE FIELD.
4. THE ADDITIONAL 1' PAVEMENT CUT BACK SHALL BE MADE AFTER BACKFILLING AND TESTING IS COMPLETE. THIS CUT SHALL BE REMOVED TO A NEAT LINE. IF THE CONTRACTORS OPERATION PRODUCES A JAGGED EDGE HE SHALL BE REQUIRED TO REMOVE ADDITIONAL PAVING UNTIL A NEAT STRAIGHT LINE IS OBTAINED.



**TRENCH PAY WIDTH**

**CONSTRUCTION STANDARDS**

STANDARD NO. SS-12

SHEET 3 OF 4

APP'D R. Salcido

DATE Oct. 11, 2023